

# EXHIBIT C

## Restoration plan

All extraction / mining area and haul road will be restored to the City of Pequot Lakes requirements.

All excavation area will be graded to contour and shape out any berms to minimize any erosion due to rain fall, four inches of black topsoil will be place on all areas. Haul road will be restored to same condition prior to extraction operation.

Vegetation will be restored by appropriate seed of grasses.

All banks of excavation area not backfilled will be sloped no steeper than 3 foot horizontal and 1 foot vertical and planted with vegetation.

Reclamation of extractive use site and designated haul road shall be complete with in one year of permit ending.